




**CEILING PLAN LEGEND**

- 6" OPEN DOWNLIGHT (RECESSED)
- ◐ 6" LENSED DOWNLIGHT (RECESSED)
- ⊗ HUNG LIGHTED EMERGENCY EXIT SIGN
- 2'X4' LIGHT FIXTURE
- ▨ 2'X2' ACOUSTIC CEILING TILE
- ▩ 2'X4' ACOUSTIC CEILING TILE

**RCP NOTES LEGEND**

- (C1) EXISTING CEILING TO REMAIN IN EXISTING RESTROOMS AND BACK OF HOUSE.
- (C2) CEILING MOUNTED MONITOR. PROVIDE DUPLEX IN CEILING.
- (C3) PROVIDE QUAD OUTLET IN CEILING ABOVE HEAT RACK.
- (C4) REPAIR EXISTING GWB CEILING AS REQUIRED.
- (C5) 3/8" MTL STUD BULKHEAD
- (C6) NEW CEILING TO MATCH HEIGHT OF EXISTING CEILING



**FLOOR PLAN LEGEND**

- ⌂ DOOR
- ▬ NEW METAL STUD WALL
- ▬ PARTITION TYPE KEY
- ▬ NEW HALF WALL PARTITION (3'-6" OR 4'-6" A.F.F.) W/16" SNEEZE GUARD 1" GYPSUM BOARD ON EACH SIDE OF 1 1/2" X 3/4" METAL STUD AT 8" O.C.
- ▬ EXISTING WALL TO REMAIN

**LIFE SAFETY LEGEND**

- 300 FT MAXIMUM TRAVEL PATH W/ DISTANCE
- LIFE SAFETY NOTES:**
- IN THE EVENT OF POWER FAILURE, AN EMERGENCY ELECTRICAL SYSTEM (NOT LESS THAN 90 MINUTES WITH STORAGE BATTERY) SHALL AUTOMATICALLY ILLUMINATE ALL AISLES, CORRIDORS, EXTERIOR EGRESS, INTERIOR EXIT DISCHARGE, AND EXTERIOR LANDINGS.
  - LIGHTING AT ALL EXTERIOR DOORS SHALL HAVE DUAL EMERGENCY LIGHTING CAPABILITY INCLUDING 90 MINUTE BATTERY BACKUP.

**PLAN NOTES LEGEND**

- (P1) NEW WALL MOUNTED MAKELINE MONITOR WITH MAKELINE CPU MOUNTED BEHIND. RIGHT EDGE OF MONITOR TO BE 12" FROM RIGHT EDGE OF MAKELINE.
- (P2) PIZZA TRACKER, MOUNTED ON SWING ARM. VERIFY LOCATION W/ OWNER.
- (P3) NEW SLAP TABLE SOFFITT MOUNTED MONITOR W/RECESSED RECEPTACLE RIGHT SIDE OF MONITOR TO BE 12" FROM SOFFIT EDGE.
- (P4) NEW MAKELINE SOFFITT MOUNTED MONITOR W/RECESSED RECEPTACLE. ALIGN LEFT EDGE OF MONITOR WITH LEFT SIDE OF MAKELINE BELOW.
- (P5) (2) MENU MONITORS. POWER AND DATA FROM ABOVE. MIN 6'-10" A.F.F. VERIFY WITH OWNER FOR FINAL LOCATION AND COORDINATION WITH HEAT RACK/CUT TABLE OVER SHELF.
- (P6) HALF WALL PARTITION 4'-0" (OR 4'-6") A.F.F. TOP WITH 6" CORIAN AND 1'-6" TEMPERED SNEEZE GUARD. BUILD WITH TABLES IN PLACE.
- (P7) CORIAN COUNTER W/ STAINLESS STEEL LEGS. SEE DETAIL 2/A2.2. ONE USB OUTLET ON CUSTOMER SIDE OF WALL.
- (P8) BLACK BOXES. PROVIDE POWER AND DATA AS REQUIRED. INSTALL PER MANUFACTURERS INSTRUCTIONS. PROVIDE 1/2" FRW PLYWOOD ON WALL BEHIND BOXES. METAL STUDS TO BE 8" O.C. BEHIND BOXES.
- (P9) NEW MIDDLEBY MARSHALL OVEN AND HOOD. CONTRACTOR TO VERIFY ALIGNMENT IN FIELD. GREASE DUCTS SHOWN ON MECHANICAL DRAWINGS. INSTALLATION OF ANSUL SYSTEM. \*MANUAL PULL STATION LOCATED 10-20 FEET AWAY. \*\*LOCAL BELL LOCATION
- (P10) PRE-FABRICATED CHILD STEPSTOOL. PROVIDE STAINLESS STEEL HANDRAIL WITH EXTENSION.
- (P11) ACCESSIBLE SEAT IN COMPLIANCE WITH VCC 2012 SECTION 1109.11.
- (P12) EXISTING STOREFRONT TO REMAIN.
- (P13) EXISTING ELECTRICAL PANELS AND EQUIPMENT TO REMAIN.

**John F. Heltzel**  
 AIA  
 A PROFESSIONAL CORPORATION  
 9389 FORESTWOOD LANE  
 MANASSAS, VIRGINIA 20110  
 PHONE: 703.748.8801  
 WWW.HELTELZELAIA.COM

**DOMINIO'S STORE #4373**  
 SPRINGFIELD, VA 22153  
 8068 ROLLING RD  
**FLOOR PLAN & RCP**

DATE:	11/11/2019
	ISSUE FOR PERMIT
1	11/22/2019
	ADDRESS COMMENTS
2	02/18/2020
	ADDRESS COMMENTS

SHEET  
**A002**